BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/RD/WORK_INDENT11498

APPROVED SCHEDULE - B

Tender Notification EE/BTP/BBMP/E-PMT/18/2013-14, Date: 13.01.2014

Improvements to Road and Drains at Poojamahalakshmi layout Cross Road in ward No 05 in Thirumenhalli Village Limits

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of DANANJAYA B R	
				In Figures	In Words
1	885	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications,	cum	125.10	Rupees One Hundred Twenty Five and Ten Paise Only
2	1296	Removing B.S Slab of Drain and stacking	Sqm	49.61	Rupees Forty Nine and Sixty One Paise Only
3	1296	Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	69.34	Rupees Sixty Nine and Thirty Four Paise Only
4	324	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete -do- 7.5 cms thick	Sqm	340.01	Rupees Three Hundred Forty and One Paise Only
5	720	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	Cum	1109.83	Rupees One Thousand One Hundred Nine and Eighty Three Paise Only
6	3600	KSRRB 500-4: providing and applying primer coat from 7.5 to 9.8 kg and 9.8 to 12.2kg per 10 sqm for surfaces of low and medium porosity respectively over prepared surface of granular base with cut bank M.C-70 or any other bitumen mixed with diesel at 10 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specificationsDo- Medium Porosity MORTH chapter 5,	Sqm	99.59	Rupees Ninety Nine and Fifty Nine Paise Only
7	90	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications.	Cum	9535.13	Rupees Nine Thousand Five Hundred Thirty Five and Thirteen Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92